


Sheet List Table	
Sheet Number	Sheet Title
G-01	COVER SHEET
G-02	NOTES AND LEGEND
V-00	EXISTING CONDITIONS
CM-101	DEMOLITION PLAN
CU-101	GRADING AND DRAINAGE PLAN
CU-201	UTILITY PROFILE
CU-501	CONSTRUCTION DETAILS
CU-502	CONSTRUCTION DETAILS
CE-101	INITIAL EROSION CONTROL PLAN
CE-102	FINAL EROSION CONTROL PLAN
CE-401	EROSION CONTROL NOTES
CE-402	EROSION CONTROL NOTES
CE-403	EROSION CONTROL NOTES
CE-404	EROSION CONTROL NOTES
CE-501	EROSION CONTROL DETAILS
CE-502	EROSION CONTROL DETAILS
CE-503	EROSION CONTROL DETAILS
CE-504	EROSION CONTROL DETAILS

LOCATION MAP
NTS

TARA BOULEVARD STORM DRAIN REHABILITATION



OWNER/DEVELOPER:
CLAYTON COUNTY WATER AUTHORITY
1600 BATTLE CREEK ROAD
MORROW, GEORGIA 30260
PHONE: (770) 961-2130

DESIGN PROFESSIONAL:
JACOBS ENGINEERING GROUP INC.
10 TENTH STREET, N.W.
ATLANTA, GEORGIA 30309
PHONE: (404) 978-7439
CONTACT: PAUL PURCELL, P.E.
LEVEL II #18856

24-HOUR CONTACT:
CONTACT: KEVIN OSBEY
PHONE: (770) 961-2130 x5504


AREA SUMMARY:
DISTURBED AREA: 1.44 AC
NEW IMPERVIOUS AREA: 0.00 AC

Jacobs.

10 TENTH STREET NW, SUITE 1400
ATLANTA, GA 30309 | T (404) 978-7600

JANUARY 2025
ISSUED FOR BID
VOLUME 3 OF 3

PROJECT DATA	
ZONING	C2
PROPOSED BUILDING SF	NA
REQUIRED PARKING SPACES (INDUSTRIAL AND ACCESSORY OFFICES)	NA
PROVIDED PARKING SPACES	NA

VICINITY MAP
NTS


PROJECT DESCRIPTION:

1. THIS PROJECT IS LOCATED AT 8405 TARA BOULEVARD IN LAND LOTS 242 OF THE 4th DISTRICT, CITY OF JONESBORO, CLAYTON COUNTY, GA.
2. THE PROPOSED DEVELOPMENT INVOLVES THE REMOVAL OF A FAILED STORM PIPE AND RE-GRADING TO CREATE A NATURAL FLOW CHANNEL. CONNECTION TO EXISTING STORM STRUCTURE WILL BE MADE BY A SHORT SECTION OF BOX CULVERT.
3. THE FLOODPLAIN LIMITS SHOWN ON THE DRAWINGS ARE FROM GA DFIRM FLOOD MAPS. THE RELEVANT FEMA FIRM PANEL IS NO. 13063C0088F DATED JUNE 7, 2017.
4. THERE ARE NO WETLANDS LOCATED ON OR WITHIN 200 FEET OF THE PROJECT SITE.
5. THERE ARE NO STATE WATERS WITHIN THE PROJECT AREA AS PER CORRESPONDENCE WITH GAEPD. DUE TO THE ONGOING EROSION, THERE IS NO WRESTED VEGETATION WITHIN THE PROPOSED AREA OF DISTURBANCE.

PROJECT GENERAL NOTES:

- B. THE PERSON ULTIMATELY RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL PRACTICES ON THIS SITE AND WHO IS TO BE CONTACTED IN THE EVENT OF A STOP WORK ORDER, IS: KEVIN OSBEY WITH PHONE # (770) 961-2130 x5504.
- B. AREAS USED AS BURIAL PITS DURING DEVELOPMENT MUST BE LOCATED OUTSIDE THE RIGHT-OF-WAY AND ARE TO BE LOCATED AND IDENTIFIED ON THE FINAL PLAT. GEORGIA DNR EPD REQUIREMENTS ARE TO BE MET: "NO PORTION OF WASTE DISPOSAL SHALL BE LOCATED WITHIN 100 LINEAR FEET OF ANY PROPERTY LINE OR ENCLOSED STRUCTURE".
- C. ANY REVISION TO THE PLANS AFTER THE INITIAL SUBMITTAL, OTHER THAN THE RESPONSE TO THE PLAN REVIEW COMMENTS, WILL BE INDICATED ON REVISIONS AND SUBMITTED WITH A WRITTEN EXPLANATION OF THE REVISIONS AND THE REASONS.
- D. ANY VARIATIONS FROM THE PERMITTED PLANS, CHANGES IN DESIGN RESULTING FROM FIELD CONDITIONS, OR SUBSTITUTION OF CONSTRUCTION MATERIALS ARE TO BE REVIEWED AND APPROVED BY THE RESPONSIBLE DESIGN ENGINEER AND CLAYTON COUNTY LAND DEVELOPMENT.
- E. PLANS ARE REVIEWED IN GENERAL. SPECIFIC DETAILS AND CALCULATIONS MAY NOT BE CHECKED. THE ENGINEERS STAMP AND SIGNATURE GUARANTEES THE ACCURACY OF THE CALCULATIONS AND DESIGN. PLAN APPROVAL DOES NOT OBLIGATE THE COUNTY TO ACCEPT THE WORK, NOR DOES IT RELIEVE THE DEVELOPER AND / OR ENGINEER FROM COMPLIANCE WITH ANY OTHER COUNTY, STATE OR FEDERAL ORDINANCES AND LAWS. PLAN APPROVAL DOES NOT RELIEVE THE DEVELOPER FROM THE RESPONSIBILITY FOR DAMAGES TO ADJACENT OR DOWNSTREAM PROPERTY RESULTING FROM THIS DEVELOPMENT.

1		2		3		4		5		6	
CIVIL LEGEND											
EXISTING		NEW		EXISTING		NEW					
× 100.00		× 100.00									
- 920 -		- 920 -									
- 922 -		- 922 -									



AS SHOWN	
VERIFY SCALE	
BAR IS ONE INCH ON ORIGINAL DRAWING.	
0	1"
DATE	JANUARY 2025
PROJ	EEXJ6937
DWG	V-00
SHEET	3 of 18

ISSUED FOR BID

o HISTORIC SIGN

DEMOLITION NOTES

- | | |
|---|--|
| <p>THE CONTRACTOR SHALL SUBMIT A DETAILED DEMOLITION PROCEDURE TO THE OWNER FOR APPROVAL AT LEAST 10 DAYS BEFORE DEMOLITION IS TO BEGIN. THE DEMOLITION PROCEDURE SHALL INCLUDE A DETAILED DESCRIPTION OF THE METHODS AND EQUIPMENT TO BE USED FOR EACH OPERATION AND THE SEQUENCE OF WORK. THE DEMOLITION PROCEDURES SHALL PROVIDE FOR SAFE CONDUCT OF WORK AND THE PROTECTION OF PROPERTY WHICH IS TO REMAIN UNDISTURBED AND COORDINATION WITH OTHER WORK OR OPERATIONS THAT MAY BE IN PROGRESS. METHODS AND SCHEDULING OF DEMOLITION ACTIVITIES MUST BE APPROVED BY THE OWNER.</p> <p>2. LOCATIONS OF EXISTING FACILITIES AND UTILITIES ARE TAKEN FROM THE SURVEY PERFORMED BY ACCURA ENGINEERING, DATED 11/28/22. THE CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING UTILITIES.</p> <p>3. THE CONTRACTOR SHALL DEMOLISH AND REMOVE THE EXISTING BUILDING, SLAB, PAVEMENT, UTILITIES, EQUIPMENT, ETC. NOTED TO BE REMOVED WITHIN THE DEMOLITION LIMITS AS SHOWN ON THIS PLAN.</p> <p>4. CONTRACTOR TO PROVIDE AND MAINTAIN NECESSARY FENCES, BARRICADES, LIGHTS, SIGNS AND OTHER TRAFFIC CONTROL MEASURES AS REQUIRED FOR THE PROTECTION AND SAFETY OF THE PUBLIC THROUGHOUT THE DEMOLITION AND CONSTRUCTION ACTIVITIES ON THE SITE.</p> | <p>THE TRAFFIC FLOW TO SURROUNDING BUSINESSES.</p> <p>6. CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES PRIOR TO THE START OF DEMOLITION ACTIVITIES.</p> <p>7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL EXISTING SERVICE CONNECTIONS FROM THE BUILDING AND PERMANENTLY CAPPING UTILITIES TO BE REMOVED WHERE REQUIRED IN ACCORDANCE WITH THE REQUIREMENTS OF THE UTILITY COMPANIES CONCERNED.</p> <p>8. CONTRACTOR SHALL SAWCUT TO FULL PAVEMENT, SIDEWALK AND CURB AND GUTTER DEPTH AT THE LIMIT OF DEMOLITION FOR REMOVAL OF PAVEMENT, SIDEWALK AND CURB AND GUTTER.</p> <p>9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE CAUSED TO ANY ADJACENT AREA NOT INTENDED FOR DEMOLITION. THE CONTRACTOR SHALL RESTORE ANY DAMAGED AREA TO PRE-CONSTRUCTION CONDITIONS.</p> <p>10. ALL SALVAGEABLE METAL MATERIALS SHALL REMAIN PROPERTY OF THE OWNER AND SHALL BE CLEANED AND STORED ON THE OWNER'S PROPERTY AS DIRECTED BY THE OWNER.</p> <p>11. NO DEBRIS FROM SITE DEMOLITION SHALL BE BURIED ON SITE. ALL MATERIAL GENERATED FROM DEMOLITION OPERATION SHALL BE PROPERLY DISPOSED OF OFFSITE.</p> <p>12. THE CONTRACTOR SHALL INSTALL ALL INITIAL EROSION AND SEDIMENTATION CONTROL MEASURES PRIOR TO DEMOLITION OPERATIONS BEGINNING.</p> |
|---|--|

SSMH=848.76
IE IN(N)=835.66
IE IN(E)=830.46
IE IN(SE)=844.91
IE IN(SW)=834.21
IE OUT=830.53

JOSEPH A JR & GLADYS F GRIMAUD
TAX PARCEL #13239D B022
TAX PARCEL #13239D B023

G-100
5/8"
RBC(eGPS)
N: 1282349.761
E: 2236588.539
Z: 858.759

SSMH=854.75
IE=NOT OBTAIN

- EXISTING SITE SECURITY FENCE TO REMAIN. CONTRACTOR TO PROVIDE ADDITIONAL MEASURES AS NEEDED TO SECURE THE WORK AREA.

— REMOVE EXISTING 112" X 75"
CORRUGATED ARCH PIPE ALONG
ESTABLISHED CREEK AS SHOWN
ON CU-101

- REMOVE EXISTING STRUCTURE
AND REPLACE WITH A NEW
STRUCTURE AS SHOWN ON
CU-101

SDMH=854.39
IE IN=847.69
TOP OF H2O=837±
BOTTOM(DIRT/DEBRIS)=829.4±

<-8'X8' BOX CULVERT
(PER GDOT PI#0007922 DRAWING#13-07)

SDMH/DWCB=857.97
IE IN=851.97
IE OUT=850.92

3K 3/US 19/47

[illegible]

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF000350 (EXP 6/30/2022)

TARA BOULEVARD STORM
DRAIN REHABILITATION
8405 TARA BLVD
JONESBORO, GA 30236

Jacobs.

CIVIL
DEMOLITION PLAN

AS SHOWN

VERIFY SCALE

BAR IS ONE INCH ON
ORIGINAL DRAWING

DATE	JANUARY 2025
------	--------------

PROJ	EEXJ6937
------	----------

DWG	CM-101
-----	--------


SHEET 4 of 18

ISSUED FOR BID

© JACOBS 2022. ALL RIGHTS RESERVED.

F. FURVELL	F. ANINOSITO	G. HENGBLE
------------	--------------	------------



REUSE OF DOCUMENTS:



© JACOBS 2022. ALL RIGHTS RESERVED.

	DATE	BY	FOR	OTHER
REUSE OF DOCUMENTS:				
THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED IN WHOLE OR IN PART FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.				

ISSUED FOR BID



NO.	DATE	DSGN	DR	CHK	APVD	P. PURCELL	C. HENSLEY	P. PURCELL
3	11/2024	ISSUED FOR BID				SA	PP	PP
2	06/2024	90% DESIGN DRAWINGS				SA	PP	PP
1	03/2024	60% DESIGN DRAWINGS				SA	PP	PP
0	01/25/24	30% DESIGN DRAWINGS				PA	PP	PP
						BY	APVD	

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF0000350 (EXP 6/30/2024)

TARA BOULEVARD STORM
DRAIN REHABILITATION
8405 TARA BLVD
JONESBORO, GA 30236

Jacobs


CIVIL
UTILITY PROFILE

AS SHOWN
VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"
DATE JANUARY 2025
PROJ EEXJ6937
DWG CU-201
SHEET 6 of 18

ISSUED FOR BID

© JACOBS 2022. ALL RIGHTS RESERVED.


THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.



PLOT TIME: 1:19 PM



ISSUED FOR BID



1

2

3

4

5

6

OWNER/DEVELOPER:

CLAYTON COUNTY WATER AUTHORITY
1600 BATTLE CREEK ROAD
MORROW, GA 30260
PHONE: (770) 961-2130

PRIMARY PERMITTEE/ OPERATOR

KEVIN OSBEY
STORMWATER UTILITY DIRECTOR
PHONE: (770) 961-2130 (EXT. 5504)
EMAIL: KEVIN.OSBEY@CCWA.US

LEVEL II CERTIFIED DESIGNER:

JACOBS ENGINEERING GROUP INC.
10TH STREET NW, SUITE 1400
ATLANTA, GA 30309
PHONE: (404) 978-7600
CONTACT: PAUL PURCELL, P.E.
LEVEL II CERT #: 18856

SITE DESCRIPTION, PURPOSE, LOCATION & CONSTRUCTION ACTIVITY: 8

THE EXISTING SITE IS COMPRISED OF DEVELOPED PROPERTY IN CLAYTON COUNTY. THE SITE IS LOCATED IN A COMMERCIAL/INDUSTRIAL AREA IN JONESBORO, GA. THE SITE IS BORDERED BY AN TARA BLVD (US-HWY 41) TO THE EAST VETERANS PKWY TO THE NORTH AND RUNS ALONG A TRIBUTARY TO FLINT RIVER.

THE PROPOSED PROJECT INVOLVES REMOVAL OF A FAILED STORM DRAIN LINE AND RE-ESTABLISHING THE NATURAL CHANNEL TO IMPROVE STORM CONVEYANCE THROUGH THE PROPERTY, GRADING, AND REPLACEMENT/REHABILITATION OF EXISTING STORM STRUCTURES

THE AREAS ADJACENT TO THE SITE ARE MAINLY COMMERCIAL PROPERTIES. EXISTING LAND CONDITIONS INCLUDE SLOPES OF 6%-10%, WITH STEEP SLOPES ALONG THE TRIBUTARY OF 60%-70% DUE TO EROSION.

PROPERTY OWNERS
8405 TARA BOULEVARD PARCEL 1234B A018
PROPERTY OWNER: ENDLESS SOLUTIONS INC. (CLAYTON COUNTY WATER AUTHORITY(CCWA)) HAS A PUBLIC NUISANCE ABATEMENT ISSUED BY THE JONESBORO MUNICIPAL COURT THAT ALLOWS CCWA ACCESS TO THE PROPERTY TO ADDRESS THE STORM DRAIN ISSUE.)

8415 TARA BOULEVARD, PARCEL 1324B A017
PROPERTY OWNER: CLAYTON COUNTY WATER AUTHORITY

TOTAL SITE AREA: 1.86 AC 5
TOTAL DISTURBED AREA: 1.44 AC

SOILS INFORMATION: 7

SOILS TYPES-DESCRIPTION	SYMBOL	PERMEABILITY
APPLYING SANDY LOAM, 6 TO 10 PERCENT SLOPES	AmC	WELL DRAINED
GWINNETT SANDY LOAM, 6 TO 10 PERCENT SLOPES ERODED	GwC2	WELL DRAINED
GWINNETT SANDY CLAY LOAM, 10 TO 25 PERCENT SLOPES, ERODED	GwE2	WELL DRAINED
URBAN LAND	UD	N/A

SOIL LOCATIONS ARE LOCATED ON ALL PHASES OF THE EROSION CONTROL PLANS CONTAINED WITHIN.

SITE RUNOFF COEFFICIENT: 45

BEFORE CONSTRUCTION - CN = 73
AFTER CONSTRUCTION - CN = 69

SITE WETLANDS/STATE WATERS:

THERE ARE NO WETLANDS LOCATED ON OR WITHIN 200 FEET OF THE PROJECT SITE.
THERE ARE NO STATE WATERS LOCATED ON OR WITHIN 200 FEET OF THE PROJECT SITE.

RECEIVING WATERS:9

RECEIVING WATERS FROM THE SITE - FLINT RIVER

DRAINAGE DESCRIPTION

THE SITE CONTAINS HEAVY SLOPES DUE TO EROSION WITH SLOPES OF 6%-10% ADJACENT TO THE PROPERTY AND 60%-70% ALONG THE CREEK BED. THE EXISTING DRAINAGE FLOWS FROM NORTH AND SOUTH TOWARDS A CREEK THAT FLOWS FROM EAST TO WEST ALONG THE CENTER OF THE SITE. MUCH OF THE RUNOFF IN PROXIMITY TO THE SITE IS COLLECTED THROUGH STORM PIPING AND DIVERTED INTO THE CREEK. THE ENTIRE DRAINAGE BASIN IS APPROXIMATELY 267-ACRES OF ON-SITE AND OFF-SITE AREA.

STORMWATER MANAGEMENT & WATER QUALITY

THE DESIGN REMOVES ALL EXISTING IMPERVIOUS AREA FROM THE PROJECT SITE. NO NEW IMPERVIOUS AREA IS PLANNED FOR THE PROJECT SITE.

29

SCHEDULE OF MAJOR ACTIVITIES						
BEGIN CONSTRUCTION	(MONTHS AFTER BEGINNING CONSTRUCTION)					
DESCRIPTION	1	2	3	4	5	6
MAINTENANCE OF ALL EROSION CONTROL MEASURES	////	////	////	////	////	////
INSTALLATION OF CNST EXIT, PERIMETER SILT FENCE, & TREE PROT. FENCE	///					
CLEARING AND GRUBBING	///					
INSTALL INTERMEDIATE EROSION CONTROL MEASURES		///				
STORM DRAIN/ CULVERT INSTALLATION		////	////			
MASS GRADING		////	////	////	////	
INSTALL FINAL PHASE EROSION CONTROL MEASURES					///	///
REMOVE TEMPORARY EROSION MEASURES						///

GENERAL EROSION CONTROL NOTES FOR ALL PHASES:

1. DURING CONSTRUCTION, THE CONTRACTOR/OWNER SHALL MAINTAIN CAREFUL SCHEDULING AND PERFORMANCE TO ENSURE THAT LAND STRIPPED OF ITS NATURAL GROUND COVER IS EXPOSED ONLY IN SMALL QUANTITIES AND THEREFORE LIMITED DURATIONS, BEFORE PERMANENT EROSION PROTECTION IS ESTABLISHED. NOTE THREE NOTIONAL ESPC PHASES ARE DESCRIBED OR SHOWN IN THESE DRAWINGS. ADDITIONAL BMPs MAY BE NECESSARY DUE TO CONTRACTOR/ OWNER CONSTRUCTION SEQUENCING AND/OR ESPCP SUB PHASES

2. INITIAL, INTERMEDIATE, AND FINAL PHASES SHOWN ON PLANS ARE A SNAPSHOT OF TYPICAL BMPs REQUIRED DURING EACH RESPECTIVE PHASE OF CONSTRUCTION. SUB PHASING WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND ADDITIONAL BMPs SHALL BE DESIGNED AND INSTALLED AS APPLICABLE TO ACTUAL CONSTRUCTION ACTIVITIES.

3. EROSION CONTROL PRACTICES SHALL MEET THE STANDARDS OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA, OR OTHER LOCAL HANDBOOKS.

4. A COPY OF THE APPLICABLE PLANS AND PERMIT SHALL BE PRESENT ON THE SITE WHENEVER LAND DISTURBANCE ACTIVITY IS IN PROGRESS.

5. PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITY, THE LIMITS OF LAND DISTURBANCE SHALL BE CLEARLY AND ACCURATELY DEMARCATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE ACTIVITY SHALL BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.

6. A STABILIZED CONSTRUCTION ENTRANCE WILL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE. THE CONSTRUCTION EXITS SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH STONE, AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEAN-OUT OF ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLE OR SITE ONTO PUBLIC ROADWAY OR INTO STORM DRAINS MUST BE REMOVED.

7. THE CONSTRUCTION OF THE SITE WILL INITIATE WITH INSTALLATION OF EROSION CONTROL MEASURES SUFFICIENT TO CONTROL SEDIMENT DEPOSITS AND EROSION. ALL SEDIMENT CONTROL WILL BE MAINTAINED UNTIL ALL UPSTREAM GROUND WITHIN THE CONSTRUCTION AREA HAS BEEN STABILIZED WITH PERMANENT VEGETATION OR PAVING.

8. CONCENTRATED FLOW AREAS AND ALL SLOPES STEEPER THAN 3:1 WITH A HEIGHT OF TEN FEET OR GREATER SHALL BE STABILIZED WITH THE APPROPRIATE EROSION CONTROL MATTING OR BLANKET, SURFACE ROUGHED AND VEGETATED WITHIN SEVEN (7) DAYS OF THEIR CONSTRUCTION.

9. ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

10. MAXIMUM CUT OR FILL SLOPES ARE 2 HORIZONTAL TO 1 VERTICAL.

11. ALL FILL SLOPES SHALL HAVE SILT FENCE PLACED AT THE SLOPE'S TOE.

12. ADDITIONAL EROSION CONTROL MEASURES SHALL BE EMPLOYED WHERE DETERMINED NECESSARY BY ACTUAL SITE CONDITIONS.

13. WHEN ANY CONSTRUCTION BORDERS A DRAINAGE SWALE/CONVEYANCE THE OPERATOR/CONTRACTOR IS RESPONSIBLE FOR REMOVING ANY EXCAVATION SPOIL DIRT, CONSTRUCTION TRASH OR DEBRIS, ETC. FROM THE DRAINAGE CONVEYANCE IN AN EXPEDITIOUS MANNER AS CONSTRUCTION PROGRESSES. OPERATOR/CONTRACTOR SHALL STABILIZE THE RESTORED AREA UPON SPOIL/DEBRIS REMOVAL.

14. FAILURE TO INSTALL, OPERATE OR MAINTAIN ALL EROSION CONTROL MEASURES MAY RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB SITE UNTIL SUCH MEASURES ARE CORRECTED BACK TO NPDES STANDARDS.

15. MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL MEASURES AND PRACTICES, WHETHER TEMPORARY OR PERMANENT, SHALL BE AT ALL TIMES THE RESPONSIBILITY OF THE PROPERTY OWNER.

16. AN UNDISTURBED BUFFER IS TO BE MAINTAINED ADJACENT TO ALL STATE WATERS ENCOUNTERED ON THE SITE. CURRENT STATE AND LOCAL REGULATIONS DETERMINE THE WIDTH OF THE BUFFER REQUIRED. EARTHWORK OPERATIONS IN THE VICINITY OF BUFFERS SHALL BE CAREFULLY CONTROLLED TO AVOID DUMPING OR SLOUGHING INTO THE BUFFER AREAS.

17. ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY VEGETATION.

18. STORM DRAIN OUTLET PROTECTION SHALL BE PLACED AT ALL OUTLET HEADWALLS AS SOON AS THE HEADWALL IS CONSTRUCTED, AS APPLICABLE.

CRITICAL WORK ZONES:

1. AT THE END OF EACH WORK DAY ALL SLOPES 2:1 OR STEEPER AND HIGHER THAN 5 FEET SHALL RECEIVE SURFACE ROUGHENING, POLYMERS, AND EROSION CONTROL MATTING.

2. ADDITIONALLY, ALL FILL SLOPES WHERE RUNOFF DRAINS TOWARDS THE TOP OF BANK SHALL RECEIVE A DIVERSION DIKE AND TEMPORARY DOWN DRAINS ALONG THE TOP OF THE SLOPE PREVENTING DRAINAGE SPILLING OVER THE EDGE AND DOWN THE FACE OF THE SLOPE.

3. THE TEMPORARY DOWN DRAINS SHALL BE CONSTRUCTED WITH PERFORATED STAND PIPES AT THE TOP OF THE SLOPE AND RECONSTRUCTED EACH DAY AS THE SLOPE INCREASES IN HEIGHT.

28

INITIAL PHASE EROSION CONTROL NOTES:

THE FOLLOWING INITIAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITY:

1. A STABILIZED CONSTRUCTION ENTRANCE WILL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE

2. IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION ENTRANCE/EXITS, ALL PERIMETER EROSION CONTROL AND STORM WATER MANAGEMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE INITIAL PHASE EROSION CONTROL PLAN.

3. SILT FENCE SHOULD BE INSTALLED AS SHOWN ON THE PLAN. THE SILT FENCE SHOULD BE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA, TABLE 6-27.1. THE SILT FENCE SHOULD BE KEPT ERECT AT ALL TIMES AND REPAIRED WHEN REQUESTED BY THE SITE INSPECTOR OR THE PROJECT DESIGN PROFESSIONAL OF RECORD. SILT SHOULD BE REMOVED WHEN ACCUMULATION REACHES ½ HEIGHT OF THE BANNER. THE PERIMETER SILT FENCE SHOULD BE INSPECTED DAILY FOR ANY FAILURES. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.

4. INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL EXISTING STORM STRUCTURES AS APPLICABLE. SEE PLAN VIEW FOR SPECIFIC TYPE OF INLET PROTECTION REQUIRED.

5. THE CONTRACTOR CAN UTILIZE CLEARED TREES AS BARRIER BRUSH SEDIMENT CONTROL IN AREAS SHOWN ON PLAN WHERE INITIAL GRADING ACTIVITIES WILL NOT OCCUR.

6. STONE/HAYBALE CHECK DAMS SHALL BE INSTALLED IN AREAS OF CONCENTRATED FLOWS AS SHOWN ON THE PLAN.

7. ADDITIONAL SILT BARRIERS MUST BE PLACED AS SHOWN ON THE PLAN AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL TAKE PLACE UNTIL SILT BARRIERS ARE INSTALLED AS SHOWN ON THE INITIAL PHASE EROSION CONTROL PLAN.

8. THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT TRAPS AND DIVERSION DIKES AS SHOWN ON PLAN. THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT TRAPS UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF THE TRAPS WHEN IT REACHES ⅓ OF THE TOTAL SEDIMENT STORAGE VOLUME.

9. IF UNFORESEEN CONDITIONS EXIST IN THE FIELD THAT WARRANT ADDITIONAL EROSION CONTROL MEASURES, THE CONTRACTOR MUST CONSTRUCT ADDITIONAL EROSION CONTROL DEVICES DEEMED NECESSARY BY THE SITE INSPECTOR, OWNER, OR DESIGN PROFESSIONAL AS PART OF THE EXISTING ESPC PLANS/DRAWINGS.

10. WITHIN 7 DAYS OF COMPLETING INSTALLATION OF INITIAL EROSION CONTROL MEASURES, THE SITE CONTRACTOR SHALL SCHEDULE AN INSPECTION BY THE PROJECT DESIGN PROFESSIONAL. NO OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE PROJECT DESIGN PROFESSIONAL APPROVES THE INSTALLATION OF SAID EROSION CONTROL MEASURES. FAILURE OF OBTAINING THIS INSPECTION IS A DIRECT VIOLATION OF THE NPDES PERMIT.

28

INTERMEDIATE PHASE EROSION CONTROL NOTES:

THE FOLLOWING EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE INTERMEDIATE PHASE OF CONSTRUCTION:

1. THE CONSTRUCTION EXITS SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH STONE, AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEAN-OUT OF ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLE OR SITE ONTO PUBLIC ROADWAY OR INTO STORM DRAIN MUST BE REMOVED.

2. SEDIMENT SHALL NOT BE WASHED INTO INLETS. IT SHALL BE REMOVED FROM BMP FEATURES, DISPOSED OF, AND STABILIZED SO THAT IT WILL NOT ENTER INLETS AGAIN.

3. EROSION CONTROL DEVICES SHALL BE INSTALLED IMMEDIATELY AFTER GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DESIGN PROFESSIONAL IMMEDIATELY.

4. THE CONTRACTOR SHALL FURNISH AND MAINTAIN ALL NECESSARY BARRICADES WHILE ROADWAY FRONTAGE IMPROVEMENTS ARE BEING MADE.

5. TYPE "S" SILT FENCE, SHOULD BE INSTALLED AT THE TOE OF ALL FILL SLOPES AND TOPSOIL/EARTH STOCKPILE AREAS. THE SILT FENCE SHOULD BE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA, TABLE 6-27.1. THE SILT FENCE SHALL BE MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED ON THE SLOPE. SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES ½ HEIGHT OF THE BARRIER. ADDITIONALLY, DIVERSION DIKES SHALL BE CONSTRUCTED ALONG THE TOP OF ALL SAID FILL SLOPES WITH THE USE OF TEMPORARY DOWN DRAINS TO CONTROL STORM WATER RUNOFF.

6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING BARRIERS AT THE TOE OF SLOPES UNDER CONSTRUCTION. THESE BARRIERS MAY BE RELOCATED AND REUSED AFTER PERMANENT SLOPE STABILIZATION BECOMES FULLY ESTABLISHED. AS THEY ARE RELOCATED, ANY DEFECTIVE MATERIALS IN THE BARRIER SHALL BE REPLACED. IN ADDITION, ALL DEBRIS AND SILT AT THE PREVIOUS LOCATION SHALL BE REMOVED.

7. ALL SLOPES STEEPER THAN 3:1 AND WITH A HEIGHT OF TEN FEET OR GREATER, AND CUTS AND FILLS WITHIN STREAM BUFFERS, SHALL BE STABILIZED WITH APPROPRIATE EROSION CONTROL MATING OR BLANKETS.

8. INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL STORM STRUCTURES AS APPLICABLE. SEE PLAN VIEW FOR SPECIFIC TYPE OF INLET PROTECTION REQUIRED.

9. STONE/HAYBALE CHECK DAMS SHALL BE INSTALLED IN AREAS OF CONCENTRATED FLOWS AS SHOWN ON THE PLAN.

10. ALL DRAINAGE SWALES SHALL BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED.

2828

FINAL PHASE EROSION CONTROL NOTES:

THE FOLLOWING EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE FINAL EROSION CONTROL PHASE OF CONSTRUCTION:

1. SEDIMENT SHALL NOT BE WASHED INTO INLETS. IT SHALL BE REMOVED FROM THE BMP FEATURES, DISPOSED OF, AND STABILIZED SO THAT IT WILL NOT ENTER THE INLETS AGAIN.

2. ALL DISTURBED AREAS SHOULD BE APPLIED WITH PERMANENT STABILIZATION COVER AS SOON AS FINAL GRADE IS ACHIEVED AND NO ADDITIONAL CONSTRUCTION IS PLANNED IN THE SUBJECT AREA.

3. WHEN FINAL STABILIZATION OCCURS, THE CONTRACTOR SHALL REMOVE ALL SILT FENCES, HAYBALE CHECK DAMS, AND INLET PROTECTION BARRIERS. ALL STORM OUTLET PROTECTION ARE TO REMAIN IN PLACE AND BE FREE OF SEDIMENT. FILTER RINGS AND STONE CHECK DAMS MAY BE REMOVED UPON FINAL STABILIZATION.

CERTIFICATION STATEMENTS

12 I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED, PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER(S) OR THE SAMPLING OF THE STORM WATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GA100001. SAMPLING MAY BE EXEMPTED IF RUNOFF LEAVES THE SITE VIA SHEET FLOW AND NO CONCENTRATED CHANNELS OR RECEIVING WATERS ARE ADJACENT TO THE SITE.

13 I ALSO CERTIFY, UNDER PENALTY OF LAW, THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY SUPERVISION.

Paul Purcell

GEORGIA LICENSED PROFESSIONAL

14 THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS, PERIMETER CONTROL BMPs AND SEDIMENT BASINS IN ACCORDANCE WITH PART IV.A.5. WITHIN 7 DAYS AFTER INSTALLATION.

15 NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

17 AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

18 WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

19 THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.

20 EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

21 ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

EROSION CONTROL AND TREE PROTECTION MEASURES SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITY AND MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.

ANY ADDITIONAL MEASURES DEEMED NECESSARY BY THE APPLICABLE AUTHORITY OR AN ON-SITE INSPECTION TEAM WILL BE INSTALLED WITHIN 7 DAYS.

SITE CONSTRUCTION NOTES:

1. SUBSTATION PAD AREA SHALL BE STABILIZED USING A THIN LAYER OF GRAVEL UNTIL COMPLETION OF SUBSTATION'S ELECTRICAL EQUIPMENT CONSTRUCTION. FOLLOWING ELECTRICAL CONSTRUCTION FINAL STABILIZATION SHALL BE GRAVEL PAD PLACED BY OTHERS AS SHOWN IN SITE PLAN. PLACEMENT OF FINAL GRAVEL OUTSIDE THE SUBSTATION GROUND GRID SHALL BE INCLUDED WITH THIS DESIGN PACKAGE AND COORDINATED WITH MEAG TO SYNC WITH OTHER CONSTRUCTION ACTIVITIES. CONTAINMENT BERMS SHALL BE CONSTRUCTED IMMEDIATELY FOLLOWING ELECTRICAL CONSTRUCTION.

2. ALL TEMPORARY MEASURES, INCLUDING Co, CWA, Fr, Sd1, Ds1 SHALL BE REMOVED UPON FINAL STABILIZATION OF GRAVEL SUBSTATION PAD.

3. CONTOUR ELEVATIONS SHOWN REPRESENT FINAL GRADE AT TOP OF GRAVEL AND/OR PAVEMENT.

4. CONTRACTOR TO CONFIRM AUTHORIZATION WITH MEAG FOR ANY ACCESS, CLEARING, DRIVEWAY, GRADING OR OTHER ENCROACHMENTS OUTSIDE THE PROPOSED PROPERTY LINE AND TRANSMISSION LINE EASEMENT SHOWN.

5. CONTRACTOR TO PROVIDE A TRAFFICABLE CONSTRUCTION DRIVE AND ACCESS ROUTE AROUND THE SITE AND TO/ALONG THE TRANSMISSION LINE EASEMENT WITH MULCH OR OTHER MATERIAL TO MINIMIZE DISTURBANCE BY CONSTRUCTION TRAFFIC. THIS DRIVE AND ROUTE SHOULD BE KEPT STABILIZED TO MINIMIZE EROSION.

6. MAINTENANCE OF ACCESS ROUTE SHALL INCLUDE EXISTING FEATURES WHICH PROVIDE ACCESS FROM THE PROPOSED WASHINGTON #03 SUBSTATION TO THE TIE-IN ALONG THE EXISTING GPC TRANSMISSION LINE, INCLUDING BUT NOT LIMITED TO DIRT AND GRAVEL ROADS, CULVERTS AND/OR FORD CROSSING. THESE FEATURES SHALL BE RESTORED TO EXISTING CONDITION OR BETTER AT CONCLUSION OF WORK. CONTRACTOR AND MEAG SHALL ENSURE ANY APPROPRIATE PERMITS OR APPROVALS ARE OBTAINED PRIOR TO ANY WORK IN THE RAIL RIGHT OF WAY.

7. CONSTRUCTION TRAFFIC IS LIMITED TO STABILIZED/MULCHED ACCESS ROUTE, EXCEPT IMMEDIATELY ADJACENT TO OR AROUND PROPOSED POLE PLACEMENT AREAS. THESE POLE PLACEMENT AREAS SHOULD HAVE ADEQUATE BMPs IN PLACE PRIOR TO CONSTRUCTION TRAFFIC, EXCEPT AS IS NECESSARY FOR INSTALLATION OF BMPs.

8. CLEAR AND IMMEDIATELY STABILIZE ALL ACCESS ROADS.

9. ACCESS ROUTES MAY REQUIRE MATTING TO PREVENT DISTURBANCE. RESTORE ACCESS ROUTE VEGETATION OR EXISTING STABILIZATION TO ORIGINAL CONDITION PRIOR TO DEMOBILIZATION.

10. IN ALL CASES, CLEARED AREAS SHOULD BE STABILIZED IMMEDIATELY FOLLOWING REMOVAL OF TIMBER MATTING OR BEFORE MOVING EQUIPMENT TO CLEAR ADDITIONAL AREA.

11. NO STAGING WITHIN WETLANDS AND STREAMS/STREAM BUFFERS.

12. ALL UTILITY WORK TO OCCUR WITHIN LIMITS OF DISTURBANCE, EXISTING POWER EASEMENTS, OR NEW SUBSTATION PARCELS/EASEMENT LIMITS.

13. ALL Sd1, Co AND Cd-S MUST BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.

14. CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND MAKING ADJUSTMENTS TO TYPE AND PLACEMENT OF BMPs THAT ARE FOUND TO CONFLICT WITH SITE FEATURES NOT NOTED OR SHOWN ON THE BASE MAP/ SURVEY INFORMATION.

15. UNLESS OTHERWISE NOTED, PREVIOUSLY IMPROVED AREAS SHALL BE RESTORED AS PER OWNER AGREEMENT AND/OR ORIGINAL CONDITIONS. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AFTER FINAL STABILIZATION.

16. COMPLETE MULCH STABILIZATION IS REQUIRED WITHIN 30 FEET OF POLE INSTALLATION, OTHERWISE A BRUSH BERM, MULCH BERM, OR Sd1 SHOULD BE INSTALLED AROUND THE OUTSIDE LIMITS OF THE POLE INSTALLATION AREA.

17. PERMITTED CLEARING AND CONSTRUCTION WITHIN WETLANDS AND STREAM BUFFERS SHALL BE PERFORMED USING: EQUIPMENT OPERATING ON TIMBER MATTING, HAND TOOLS, OR SPECIAL EQUIPMENT THAT APPLIES SOIL PRESSURE EQUAL TO OR LESS THAN LOADED TIMBER MATTING. NO GRUBBING WITHIN WETLANDS OR STREAM BUFFERS. IN ALL CASES CLEARED AREAS SHOULD BE STABILIZED IMMEDIATELY FOLLOWING REMOVAL OF TIMBER MATTING OR BEFORE MOVING EQUIPMENT TO CLEAR ADDITIONAL AREA. THE MAXIMUM CLEARED AREA PRIOR TO STABILIZATION SHALL BE LESS THAN ONE ACRE.

18. CLEARING AND GRUBBING ACTIVITIES IN STREAM BUFFER AND WETLAND AREAS SHALL INVOLVE MINIMAL SOIL DISTURBANCE. ANY DISTURBED SOIL SHOULD BE RETURNED TO PRE-CONSTRUCTION CONTOURS AND INCLUDE THE APPROPRIATE PLANTINGS.

22

LEVEL II CERT. # 18856

GA LIC # PEF000350 (EXP 6/30/2026)

FILENAME: CE-501 EROSION CONTROL NOTES

PLOT DATE: 2024-12-23

PLOT TIME: 1:23 PM

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF000350 (EXP 6/30/2024)

TARA BOULEVARD STORM DRAIN REHABILITATION
8405 TARA BLVD
JONESBORO, GA 30236

11/2024

08/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

APVD

DR

P. PURCELL

P. AKINOSHIO

C. HENSLEY

P. PURCELL

AS SHOWN

VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.

DATE JANUARY 2025

PROJ EEXJ6937

DWG CE-401

SHEET 11 of 18

ISSUED FOR BID

REUSE OF DOCUMENTS: THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.

© JACOBS 2022. ALL RIGHTS RESERVED.

J:\EEXJ6937\500.DESIGN\410.CAD\712SHTS

1

2

3

4

5

6

NON-STORM WATER DISCHARGES

ALL NON-STORM WATER DISCHARGES WILL BE ROUTED THROUGH ON SITE BMPS AND THE STORM WATER MANAGEMENT SYSTEM WHERE POSSIBLE. THESE DISCHARGES INCLUDE FLUSHING OF WATER AND FIRE LINES, IRRIGATION WATER, GROUND WATER DEWATERING OF PITS OR DEPRESSIONS WITHIN THE CONSTRUCTION SITE AND RINSE OFF WATER OF NON-TOXIC MATERIALS.

OTHER CONTROLS

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

WASTE MATERIALS

ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL SOLID WASTE MANAGEMENT REGULATIONS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED A MINIMUM OF ONCE PER WEEK OR MORE OFTEN IF NECESSARY AND TRASH WILL BE HAULED AS REQUIRED BY LOCAL REGULATIONS. NO CONSTRUCTION WASTE WILL BE BURIED ONSITE. ALL PERSONNEL WILL BE INSTRUCTED ON PROPER PROCEDURES FOR WASTE DISPOSAL. A NOTICE STATING THESE PRACTICES WILL BE POSTED AT THE JOBSITE AND THE CONTRACTOR WILL BE RESPONSIBLE FOR SEEING THAT THESE PROCEDURES ARE FOLLOWED.

BUILDING MATERIALS, BUILDING PRODUCTS, CONSTRUCTION WASTES, TRASH, LANDSCAPE MATERIALS, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS STORED ONSITE AND EXPOSED TO PRECIPITATION SHALL BE COVERED WITH PLASTIC SHEETING OR A CONSTRUCTED TEMPORARY COVER.

HAZARDOUS WASTES

ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL STATE AND/OR FEDERAL REGULATIONS AND BY THE MANUFACTURER OF SUCH PRODUCTS. THE JOB SITE SUPERINTENDENT, WHO WILL ALSO BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED, WILL INSTRUCT SITE PERSONNEL IN THESE PRACTICES. MATERIAL SAFETY DATA SHEETS (MSDS'S) FOR EACH SUBSTANCE WITH HAZARDOUS PROPERTIES THAT IS USED ON THE JOB SITE WILL BE OBTAINED AND USED FOR THE PROPER MANAGEMENT OF POTENTIAL WASTES THAT MAY RESULT FROM THESE PRODUCTS. AN MSDS WILL BE POSTED IN THE IMMEDIATE AREA WHERE SUCH PRODUCT IS STORED AND/OR USED AND ANOTHER COPY OF EACH MSDS WILL BE MAINTAINED IN THE ESPCP FILE AT THE JOB SITE CONSTRUCTION TRAILER OFFICE. EACH EMPLOYEE WHO MUST HANDLE A SUBSTANCE WITH HAZARDOUS PROPERTIES WILL BE INSTRUCTED ON THE USE OF MSDS SHEETS AND THE SPECIFIC INFORMATION IN THE APPLICABLE MSDS FOR THE PRODUCT HE/SHE IS USING, PARTICULARLY REGARDING SPILL CONTROL TECHNIQUES. THE CONTRACTOR WILL IMPLEMENT THE SPILL PREVENTION CONTROL AND COUNTERMEASURES (SPCC) PLAN FOUND WITHIN THIS ESPCP AND WILL TRAIN ALL PERSONNEL IN THE PROPER CLEANUP AND HANDLING OF SPILLED MATERIALS. NO SPILLED HAZARDOUS MATERIALS OR HAZARDOUS WASTES WILL BE ALLOWED TO COME IN CONTACT WITH STORM WATER DISCHARGES. IF SUCH CONTACT OCCURS, THE STORM WATER DISCHARGE WILL BE CONTAINED ON SITE UNTIL APPROPRIATE MEASURES IN COMPLIANCE WITH STATE AND FEDERAL REGULATIONS ARE TAKEN TO DISPOSE OF SUCH CONTAMINATED STORMWATER. IT SHALL BE THE RESPONSIBILITY OF THE JOB SITE SUPERINTENDENT TO PROPERLY TRAIN ALL PERSONNEL IN THE USE OF THE SPCC PLAN.

SANITARY WASTES

A MINIMUM OF ONE PORTABLE SANITARY UNIT WILL BE PROVIDED FOR EVERY TEN (10) WORKERS ON THE SITE. ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONE TIME PER WEEK BY A LICENSED PORTABLE FACILITY PROVIDER IN COMPLETE COMPLIANCE WITH LOCAL AND STATE REGULATIONS. ALL SANITARY WASTE UNITS WILL BE LOCATED IN AN AREA WHERE THE LIKELIHOOD OF THE UNIT CONTRIBUTING TO STORM WATER DISCHARGE IS NEGLIGIBLE. ADDITIONAL CONTAINMENT BMP'S MUST BE IMPLEMENTED SUCH AS GRAVEL BAGS OR SPECIALLY DESIGNED PLASTIC SKID CONTAINERS AROUND THE BASE TO PREVENT WASTES FROM CONTRIBUTING TO STORM WATER DISCHARGES. THE LOCATION OF SANITARY WASTE UNITS MUST BE IDENTIFIED ON THE EROSION CONTROL PLAN INTERMEDIATE PHASE SHEET(S) BY THE CONTRACTOR ONCE THE LOCATIONS HAVE BEEN DETERMINED.

OFFSITE VEHICLE TRACKING

A STABILIZED CONSTRUCTION EXIT HAS BEEN PROVIDED TO HELP REDUCE VEHICLE TRACKING OF SEDIMENT, SEE INCLUDED PAGES FOR CONSTRUCTION EXIT LOCATION AND DETAILS. THE PAVED STREET ADJACENT TO WILL BE INSPECTED DAILY FOR TRACKING OF MUD, DIRT OR ROCK. DUMP TRUCKS HAULING MATERIAL FROM CONSTRUCTION SITE WILL BE COVERED WITH A TARPULIN.

SPILL PREVENTION

PRACTICES SUCH AS GOOD HOUSEKEEPING, PROPER HANDLING OF HAZARDOUS PRODUCTS, AND PROPER SPILL CONTROL PRACTICES WILL BE FOLLOWED TO REDUCE THE RISK OF SPILLS AND SPILLS FROM DISCHARGING INTO STORM WATER RUNOFF.

GOOD HOUSEKEEPING

QUANTITIES OF PRODUCTS STORED ONSITE WILL BE LIMITED TO THE AMOUNT NEEDED FOR THE JOB.

PRODUCTS AND MATERIALS WILL BE STORED IN A NEAT, ORDERLY MANNER IN APPROPRIATE CONTAINERS PROTECTED FROM RAINFALL, WHERE POSSIBLE.

PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH MANUFACTURER LABELS LEGIBLE AND VISIBLE.

PRODUCT MIXING DISPOSAL AND DISPOSAL OF PRODUCT CONTAINERS WILL BE ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

THE CONTRACTOR WILL INSPECT SUCH MATERIALS TO ENSURE PROPER USE STORAGE AND DISPOSAL.

PRODUCT SPECIFIC PRACTICES

PETROLEUM BASED PRODUCTS: CONTAINERS FOR PRODUCTS SUCH AS FUELS, LUBRICANTS AND TARS WILL BE INSPECTED DAILY FOR LEAKS AND SPILLS. THIS INCLUDES ON-SITE VEHICLE AND MACHINERY DAILY INSPECTIONS AND REGULAR PREVENTATIVE MAINTENANCE OF SUCH EQUIPMENT. EQUIPMENT MAINTENANCE AREAS WILL BE LOCATED AWAY FROM STATE WATER, NATURAL DRAINS, AND STORM WATER DRAINAGE INLETS. IN ADDITION, TEMPORARY FUELING TANKS SHALL HAVE A SECONDARY CONTAINMENT LINER TO PREVENT/MINIMIZE SITE CONTAMINATION. DISCHARGE OF OILS, FUELS, AND LUBRICANTS IS PROHIBITED. PROPER DISPOSAL METHODS WILL INCLUDE COLLECTION IN A SUITABLE CONTAINER AND DISPOSAL AS REQUIRED BY LOCAL AND STATE REGULATIONS.

PAINTS/FINISHES/SOLVENTS: ALL PRODUCTS WILL BE STORED IN TIGHTLY SEALED ORIGINAL CONTAINERS WHEN NOT IN USE. EXCESS PRODUCT WILL NOT BE DISCHARGED TO THE STORM WATER COLLECTION SYSTEM. EXCESS PRODUCT, MATERIALS USED WITH THESE PRODUCTS AND PRODUCT CONTAINERS WILL BE DISPOSED OF ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.

CONCRETE TRUCK WASHING: THE PLAN INCLUDES BEST MANAGEMENT PRACTICES FOR CONCRETE WASHDOWN OF TOOLS, CONCRETE MIXER CHUTES, HOPPER AND REAR OF THE TRUCKS. WASH DOWN OF CONCRETE TRUCK DRUM AT THE CONSTRUCTION SITE IS PROHIBITED.

CONCRETE MIXER CHUTES, HOPPER AND REAR OF THE TRUCKS. WASH DOWN OF CONCRETE TRUCK DRUM AT THE CONSTRUCTION SITE IS PROHIBITED.

FERTILIZER/HERBICIDES: THESE PRODUCTS WILL BE APPLIED AT RATES THAT DO NOT EXCEED THE MANUFACTURER'S SPECIFICATIONS OR ABOVE. SEE GUIDELINES SET FORTH IN THE CROP ESTABLISHMENT OR IN THE GSWCC MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA. ANY STORAGE OF THESE MATERIALS WILL BE UNDER ROOF IN SEALED CONTAINERS.

BUILDING MATERIALS: NO BUILDING OR CONSTRUCTION MATERIALS WILL BE BURIED OR DISPOSED OF ONSITE. ALL SUCH MATERIAL WILL BE DISPOSED OF USING PROPER WASTE DISPOSAL PROCEDURES.

SPILL CLEANUP AND CONTROL PRACTICES:

LOCAL STATE AND MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND PROCEDURES WILL BE MADE AVAILABLE TO SITE PERSONNEL.

MATERIAL AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS. TYPICAL MATERIALS AND EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWDUST AND PROPERLY LABELED PLASTIC AND METAL WASTE CONTAINERS.

SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO PREVENT FUTURE SPILLS.

ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE AND FEDERAL REGULATIONS.

FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER), THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802 OR 1-202-426-2675.

FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802 OR 1-202-426-2675.

FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTED, THE GEORGIA EPD WILL BE CONTACTED WITHIN 24 HOURS.

FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED.

THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 GALLONS OF PETROLEUM IS STORED ONSITE (THIS INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS A CAPACITY GREATER THAN 680 GALLONS. THE CONTRACTOR WILL NEED A SPILL PREVENTION CONTAINMENT AND COUNTERMEASURES PLAN PREPARED BY THAT LICENSED PROFESSIONAL.

MULCH STORAGE REQUIREMENT:

MULCH STORAGE MUST COMPLY WITH THE FOLLOWING SECTION OF THE STANDARD FIRE PREVENTION CODE. SECTION 502.3.1 NO PERSON SHALL STORE IN ANY BUILDING OR UPON ANY PREMISES IN EXCESS OF 2,500 CUFT. GROSS VOLUME OF COMBUSTIBLE EMPTY PACKING CASES, BOXES, BARRELS OR SIMILAR CONTAINERS, OR RUBBER TIRES, RUBBER OR CORK OR OTHER SIMILARLY COMBUSTIBLE MATERIALS WITHOUT A PERMIT.

SAMPLING PLAN:

SAMPLING OF THE RECEIVING WATER BODY WAS DETERMINED TO OFFER THE MOST ECONOMICAL AND SIMPLISTIC MEASURE OF POTENTIAL CONSTRUCTION RELATED POLLUTION. ONE UPSTREAM & DOWNSTREAM MONITORING LOCATION IS CONSIDERED NECESSARY TO ASSESS THE CONTRIBUTORY EFFECTS OF THE PROPOSED CONSTRUCTION. A MONITORING POINT WILL BE PLACED AT EACH LOCATION (LABELED 1A & 1B). SAMPLING LOCATIONS ARE SHOWN ON USGS MAP ON THIS SHEET.

SAMPLING PROCEDURES:

ALL SAMPLING SHALL BE COLLECTED BY "GRAB SAMPLES" AND THE ANALYSIS OF THESE SAMPLES MUST BE CONDUCTED IN ACCORDANCE WITH METHODOLOGY AND TEST PROCEDURES ESTABLISHED BY 40 CFR PART 136 (UNLESS OTHER TEST PROCEDURES HAVE BEEN APPROVED); THE GUIDANCE DOCUMENT TITLED "NPDES STORM WATER SAMPLING GUIDANCE DOCUMENT, EPA 833-B-92-001" AND GUIDANCE DOCUMENTS THAT MAY BE PREPARED BY THE EPD.

SAMPLE CONTAINERS SHOULD BE LABELED PRIOR TO COLLECTING THE SAMPLES.

SAMPLES SHOULD BE WELL MIXED BEFORE TRANSFERRING TO A SECONDARY CONTAINER.

LARGE MOUTH, WELL CLEANED AND RINSED GLASS OR PLASTIC JARS SHOULD BE USED FOR COLLECTING SAMPLES. THE JARS SHOULD BE CLEANED THOROUGHLY TO AVOID CONTAMINATION.

MANUAL, AUTOMATIC OR RISING STAGE SAMPLING MAY BE UTILIZED. SAMPLES REQUIRED BY THIS PERMIT SHOULD BE ANALYZED IMMEDIATELY, BUT IN NO CASE LATER THAN 48 HOURS AFTER COLLECTION. HOWEVER, SAMPLES FROM AUTOMATIC SAMPLERS MUST BE COLLECTED NO LATER THAN THE NEXT BUSINESS DAY AFTER THEIR ACCUMULATION, UNLESS FLOW THROUGH AUTOMATED ANALYSIS IS UTILIZED. IF AUTOMATIC SAMPLING IS UTILIZED AND THE AUTOMATIC SAMPLER IS NOT ACTIVATED DURING THE QUALIFYING EVENT, THE PERMITTEE MUST UTILIZE MANUAL SAMPLING OR RISING STAGE SAMPLING DURING THE NEXT QUALIFYING EVENT. DILUTION OF SAMPLES IS NOT REQUIRED. SAMPLES MAY BE ANALYZED DIRECTLY WITH A PROPERLY CALIBRATED TURBIDIMETER. SAMPLES ARE NOT REQUIRED TO BE COOLED.

SAMPLING AND ANALYSIS OF THE RECEIVING WATER(S) OR OUTFALLS BEYOND THE MINIMUM FREQUENCY STATED IN THIS PERMIT MUST BE REPORTED TO EPD AS SPECIFIED IN PART IV.E. OF THE NPDES PERMIT.

THE FOLLOWING EVENTS SHALL BE SAMPLED:

THE PRIMARY PERMITTEE MUST SAMPLE IN ACCORDANCE WITH THE PLAN AT LEAST ONCE FOR EACH RAINFALL EVENT DESCRIBED BELOW. FOR A QUALIFYING EVENT, THE PERMITTEE SHALL SAMPLE AT THE BEGINNING OF ANY STORM WATER DISCHARGE TO A MONITORED RECEIVING WATER AND/OR FROM A MONITORED OUTFALL LOCATION WITHIN IN FORTY-FIVE (45) MINUTES OR AS SOON AS POSSIBLE.

HOWEVER, WHERE MANUAL AND AUTOMATIC SAMPLING ARE IMPOSSIBLE (AS DEFINED IN THE NPDES PERMIT), OR ARE BEYOND THE PERMITTEE'S CONTROL, THE PERMITTEE SHALL TAKE SAMPLES AS SOON AS POSSIBLE, BUT IN NO CASE MORE THAN TWELVE (12) HOURS AFTER THE BEGINNING OF THE STORM WATER DISCHARGE.

SAMPLING BY THE PERMITTEE SHALL OCCUR FOR THE FOLLOWING EVENTS:

FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR FROM AN OUTFALL, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH WITH A STORM WATER DISCHARGE THAT OCCURS DURING NORMAL BUSINESS HOURS AS DEFINED IN THE NPDES PERMIT AFTER ALL CLEARING AND GRUBBING OPERATIONS HAVE BEEN COMPLETED, BUT PRIOR TO COMPLETION OF MASS GRADING OPERATIONS, IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE SAMPLING LOCATION;

IN ADDITION TO (A) ABOVE, FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR FROM AN OUTFALL, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH WITH A STORM WATER DISCHARGE THAT OCCURS DURING NORMAL BUSINESS HOURS AS DEFINED IN THE NPDES PERMIT EITHER 90 DAYS AFTER THE FIRST SAMPLING EVENT OR AFTER ALL MASS GRADING OPERATIONS HAVE BEEN COMPLETED, BUT PRIOR TO SUBMITTAL OF A 'NOT', IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE SAMPLING LOCATION, WHICHEVER COMES FIRST;

AT THE TIME OF SAMPLING PERFORMED PURSUANT TO (A) AND (B) ABOVE, IF BMPS IN ANY AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR FROM AN OUTFALL ARE NOT PROPERLY DESIGNED, INSTALLED, AND MAINTAINED, CORRECTIVE ACTION SHALL BE DEFINED AND IMPLEMENTED WITHIN TWO (2) BUSINESS DAYS, AND TURBIDITY SAMPLES SHALL BE TAKEN FROM DISCHARGES FROM THAT AREA OF THE SITE FOR EACH SUBSEQUENT RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH DURING NORMAL BUSINESS HOURS" UNTIL THE SELECTED TURBIDITY STANDARD IS ATTAINED, OR UNTIL POST-STORM EVENT INSPECTIONS DETERMINE THAT BMPS ARE PROPERLY DESIGNED, INSTALLED AND MAINTAINED;

WHERE SAMPLING PURSUANT TO (A), (B), (C) ABOVE IS REQUIRED BUT NOT POSSIBLE (OR NOT REQUIRED BECAUSE THERE WAS NO DISCHARGE), THE PERMITTEE, IN ACCORDANCE WITH PART IV.D.4.(6), MUST INCLUDE A WRITTEN JUSTIFICATION IN THE INSPECTION REPORT OF WHY SAMPLING WAS NOT PERFORMED. PROVIDING THIS JUSTIFICATION DOES NOT RELIEVE THE PERMITTEE OF ANY SUBSEQUENT SAMPLING OBLIGATIONS UNDER (A), (B), OR (C) ABOVE; AND

EXISTING CONSTRUCTION ACTIVITIES, I.E., THOSE THAT ARE OCCURRING ON OR BEFORE THE EFFECTIVE DATE OF THIS PERMIT, THAT HAVE MET THE SAMPLING REQUIRED BY (A) ABOVE SHALL SAMPLE IN ACCORDANCE WITH (B). THOSE EXISTING CONSTRUCTION ACTIVITIES THAT HAVE MET THE SAMPLING REQUIRED BY (B) ABOVE SHALL NOT BE REQUIRED TO CONDUCT ADDITIONAL SAMPLING OTHER THAN AS REQUIRED BY (C) ABOVE.

"NOTE THAT THE PERMITTEE MAY CHOOSE TO MEET THE REQUIREMENTS OF (A) AND (B) ABOVE BY COLLECTING TURBIDITY SAMPLES FROM ANY RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR SAMPLING AT ANY TIME OF THE DAY OR WEEK.

MONITORING RESULTS:

THE RECEIVING WATER SUPPORTS WARM WATER FISHERIES. THE PRIMARY PERMITTEE HAS ELECTED TO SAMPLE UPSTREAM AND DOWNSTREAM LOCATIONS. THE CHANGE IN NTU VALUES SHALL NOT EXCEED 25 NTU.

Warm Water (Supporting Warm Water Fisheries)

Surface Water Drainage Area, square miles

0-4.99 5-9.99 10-24.99 25-49.99 50-99.99 100-249.99 250-499.99 500+

Site

1.00-10 75 150 200 400 750 750 750

10.01-25 50 100 100 200 300 500 750 750

25.01-50 50 50 100 100 200 300 750 750

50.01-100 50 50 50 100 100 150 300 600

100.01+ 50 50 50 50 50 100 200 100

TOTAL SITE AREA: 1.86 AC

TOTAL DISTURBED AREA: 1.44 AC

THE ENTIRE DRAINAGE BASIN IS APPROXIMATELY 267-ACRES OF ON-SITE AND OFF-SITE AREA.

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF000350 (EXP 6/30/2024)

TARA BOULEVARD STORM
DRAIN REHABILITATION
8405 TARA BLVD
JONESBORO, GA 30236

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF000350 (EXP 6/30/2024)

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

11/2024

06/2024

03/2024

01/25/24

NO.

DATE

ISSUED FOR BID

90% DESIGN DRAWINGS

60% DESIGN DRAWINGS

30% DESIGN DRAWINGS

REVISION

CHK

DR

DSGN

3

2

1

0

NO.

DATE

INSPECTIONS

DESIGN PROFESSIONAL

1) THE DESIGN PROFESSIONAL WHO PREPARED THIS EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN IS REQUIRED TO INSPECT THE INSTALLATION OF THE BMPs WITHIN SEVEN (7) AFTER INITIAL PERIMETER CONTROLS HAVE BEEN INSTALLED.

PRIMARY PERMITTEE

1) EACH DAY WHEN ANY TYPE OF CONSTRUCTION ACTIVITY HAS TAKEN PLACE AT A PRIMARY PERMITTEE'S SITE, CERTIFIED PERSONNEL PROVIDED BY THE PRIMARY PERMITTEE SHALL INSPECT: (A) ALL AREAS AT THE PRIMARY PERMITTEE'S SITE WHERE PETROLEUM PRODUCTS ARE STORED, USED, OR HANDLED FOR SPILLS AND LEAKS FROM VEHICLES AND EQUIPMENT, AND (B) ALL LOCATIONS AT THE PRIMARY PERMITTEE'S SITE WHERE VEHICLES ENTER OR EXIT THE SITE FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING. THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

2) MEASURE RAINFALL ONCE EVERY 24 HOURS EXCEPT ANY NON-WORKING SATURDAY, NON-WORKING SUNDAY, AND NON-WORKING FEDERAL HOLIDAY UNTIL A NOTICE OF TERMINATION IS SUBMITTED. MEASUREMENT OF RAINFALL MAY BE SUSPENDED IF ALL AREAS OF THE SITE HAVE UNDERGONE FINAL STABILIZATION OR ESTABLISHED A CROP OF ANNUAL VEGETATION AND A SEEDING OF TARGET PERENNIALS APPROPRIATE FOR THE REGION.

3) CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT THE FOLLOWING AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.5 INCHES RAINFALL OR GREATER (UNLESS SUCH STORM ENDS AFTER 5:00 PM ON ANY FRIDAY OR ON ANY NON-WORKING SATURDAY, NON-WORKING SUNDAY, OR ANY NON-WORKING FEDERAL HOLIDAY IN WHICH CASE THE INSPECTION SHALL BE COMPLETED BY THE END OF THE NEXT BUSINESS DAY AND/OR WORKING DAY, WHICHEVER OCCURS FIRST): (A) DISTURBED AREAS OF THE PRIMARY PERMITTEE'S CONSTRUCTION SITE, (B) AREAS USED BY THE PRIMARY PERMITTEE FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION, AND (C) STRUCTURAL CONTROL MEASURES. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN APPLICABLE TO THE PRIMARY PERMITTEE'S SITE SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S). FOR AREAS OF A SITE THAT HAVE UNDERGONE FINAL STABILIZATION OR ESTABLISHED A CROP OR ANNUAL VEGETATION AND A SEEDING OF TARGET PERENNIALS APPROPRIATE FOR THE REGION, THE PERMITTEE MUST COMPLY WITH PART IV.D.4.a.(4) OF THE GENERAL NPDES PERMIT. THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

4) CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT AT LEAST ONCE PER MONTH DURING THE TERM OF THIS PERMIT (I.E. UNTIL A NOTICE AT TERMINATION IS RECEIVED BY EPD) THE AREAS OF THE SITE THAT HAVE UNDERGONE FINAL STABILIZATION OR ESTABLISHED A CROP OR ANNUAL VEGETATION AND A SEEDING OF TARGET PERENNIALS APPROPRIATE FOR THE REGION. THESE AREAS SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM AND THE RECEIVING WATER(S). EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S).

5) BASED ON THE RESULTS OF EACH INSPECTION, THE SITE DESCRIPTION AND THE POLLUTION PREVENTION AND CONTROL MEASURES IDENTIFIED IN THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN, THE PLAN SHALL BE REVISED AS APPROPRIATE NOT LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION. IMPLEMENTATION OF SUCH CHANGES SHALL BE MADE AS SOON AS PRACTICAL BUT IN NO CASE LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION.

6) A REPORT OF EACH INSPECTION THAT INCLUDES THE NAME(S) OF CERTIFIED PERSONNEL MAKING EACH INSPECTION, THE DATE(S) OF EACH INSPECTION, CONSTRUCTION PHASE (I.E. INITIAL, INTERMEDIATE, OR FINAL), MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN, AND ACTIONS TAKEN IN ACCORDANCE WITH PART IV.D.4.a.(5) OF THE GENERAL NPDES PERMIT SHALL BE MADE AND RETAINED AT THE SITE OR BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION UNTIL THE ENTIRE SITE OR THAT PORTION OF A CONSTRUCTION PROJECT THAT HAS BEEN PERSESS HAS UNDERGONE FINAL STABILIZATION AND A NOTICE OF TERMINATION IS SUBMITTED TO EPD. SUCH REPORTS SHALL BE READILY AVAILABLE BY THE END OF THE SECOND BUSINESS DAY AND/OR WORKING DAY AND SHALL IDENTIFY ALL INCIDENTS OF BEST MANAGEMENT PRACTICES THAT HAVE NOT BEEN PROPERLY INSTALLED AND/OR MAINTAINED AS DESCRIBED IN THE PLAN, WHERE THE REPORT DOES NOT IDENTIFY ANY INCIDENTS, THE INSPECTION REPORT SHALL CONTAIN A CERTIFICATION THAT THE BEST MANAGEMENT PRACTICES ARE IN COMPLIANCE WITH THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN. THE REPORT SHALL BE SIGNED IN ACCORDANCE WITH PART V.G.2. OF THE GENERAL NPDES PERMIT.

Maintenance

REGULAR COMPREHENSIVE SITE INSPECTIONS OF EROSION AND SEDIMENTATION CONTROLS WILL BE PERFORMED. A QUALIFIED PROFESSIONAL WILL PERFORM ALL INSPECTION DUTIES OR WILL SUPERVISE. AT ALL TIMES, ANOTHER TRAINED INDIVIDUAL. THE PRIMARY PERMITTEE WILL OVERSEE ALL INSPECTIONS AND IMMEDIATELY BE INFORMED OF ANY CONCERNS OR PROBLEMS. IF, THROUGH THE COURSE OF INSPECTION, IT IS DETERMINED INADEQUATE, THE APPLICABLE PORTION OF THE PLAN WILL BE REVISED AND REVISIONS SHALL BE FULLY IMPLEMENTED WITHIN SEVEN CALENDAR DAYS FOLLOWING THE INSPECTION.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.

NPDES NOTES:

1. EXCEPT AS PROVIDED IN PART IV.(III) OF THE NPDES PERMIT, NO CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED WITHIN A 25 FOOT BUFFER ALONG THE BANKS OF ALL STATE WATERS, AS MEASURED HORIZONTALLY FROM THE POINT WHERE VEGETATION HAS BEEN WRESTED BY NORMAL STREAM FLOW OR WAVE ACTION, EXCEPT WHERE THE DIRECTOR HAS DETERMINED TO ALLOW A VARIANCE THAT IS AT LEAST AS PROTECTIVE OF NATURAL RESOURCES AND THE ENVIRONMENT IN ACCORDANCE WITH THE PROVISIONS OF O.C.G.A. 12-7-6, OR WHERE A DRAINAGE STRUCTURE OR A ROADWAY DRAINAGE STRUCTURE MUST BE CONSTRUCTED, PROVIDED THAT ADEQUATE EROSION CONTROL MEASURES ARE INCORPORATED IN THE PROJECT PLANS AND SPECIFICATIONS AND ARE IMPLEMENTED, OR ALONG ANY EPHEMERAL STREAM, OR WHERE BULKHEADS AND SEAWALLS MUST BE CONSTRUCTED TO PREVENT EROSION OF THE SHORELINE ON LAKE OCONEE AND LAKE SINCLAIR. PROVIDED THAT ADEQUATE EROSION CONTROL MEASURES ARE INCORPORATED INTO THE PROJECT PLANS AND SPECIFICATIONS ARE IMPLEMENTED,THE BUFFER SHALL NOT APPLY TO THOSE LAND-DISTURBING ACTIVITIES OUTLINED IN SECTION IV.1.1-IV.1.8.

2. NO CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED WITHIN A 50 FOOT BUFFER, AS MEASURED HORIZONTALLY FROM THE POINT WHERE VEGETATION HAS BEEN WRESTED BY NORMAL STREAM FLOW OR WAVE ACTION, ALONG THE BANKS OF ANY STATE WATERS CLASSIFIED AS 'TROUT STREAMS' EXCEPT WHEN APPROVAL IS GRANTED BY THE DIRECTOR FOR ALTERNATE BUFFER REQUIREMENTS IN ACCORDANCE WITH THE PROVISIONS OF O.C.G.A. 12-7-6, OR WHERE A ROADWAY DRAINAGE STRUCTURE MUST BE CONSTRUCTED; PROVIDED, HOWEVER, THAT SMALL SPRINGS AND STREAMS CLASSIFIED AS 'TROUT STREAMS' WHICH DISCHARGE AN AVERAGE ANNUAL FLOW OF 25 GALLONS PER MINUTE OR LESS SHALL HAVE A 25 FOOT BUFFER OR THEY MAY BE PIPED, AT THE DISCRETION OF THE PERMITTEE, PURSUANT TO THE TERMS OF A RULE PROVIDING FOR A GENERAL VARIANCE PROMULGATED BY THE BOARD OF NATURAL RESOURCES INCLUDING NOTIFICATION OF SUCH TO EPD AND THE LOCAL ISSUING AUTHORITY OF THE LOCATION AND EXTENT OF THE PIPING AND PRESCRIBED METHODOLOGY FOR MINIMIZING THE IMPACT OF SUCH PIPING AND FOR MEASURING THE VOLUME OF WATER DISCHARGED BY THE STREAM. ANY SUCH PIPE MUST STOP SHORT OF THE DOWNSTREAM PERMITTEE'S PROPERTY, AND THE PERMITTEE MUST COMPLY WITH THE BUFFER REQUIREMENT FOR ANY ADJACENT TROUT STREAMS. PROVIDED THAT ADEQUATE EROSION CONTROL MEASURES ARE INCORPORATED INTO THE PROJECT PLANS AND SPECIFICATIONS ARE IMPLEMENTED,THE BUFFER SHALL NOT APPLY TO THOSE LAND-DISTURBING ACTIVITIES OUTLINED IN SECTION IV.1.1-IV.1.8.

3. EXCEPT AS PROVIDED ABOVE, FOR BUFFERS REQUIRED PURSUANT TO PART IV.(I), AND (II), OF THE NPDES PERMIT, NO CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED WITHIN A BUFFER AND A BUFFER SHALL REMAIN IN ITS NATURAL, UNDISTURBED, STATE OF VEGETATION UNTIL ALL LAND DISTURBING ACTIVITIES ON THE CONSTRUCTION SITE ARE COMPLETED. DURING COVERAGE UNDER THIS PERMIT, A BUFFER CANNOT BE THINNED OR TRIMMED OF VEGETATION AND A PROTECTIVE VEGETATIVE COVER MUST REMAIN TO PROTECT WATER QUALITY AND AQUATIC HABITAT AND A NATURAL CANOPY MUST BE LEFT IN SUFFICIENT QUANTITY TO KEEP SHADE ON THE STREAM BED.

4. THE PROJECT SITE DOES NOT DISCHARGE STORMWATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS, ANY PORTION OF AN BIOTA IMPAIRED STREAM SEGMENT.

RECORD RETENTION

PRIMARY PERMITTEE
THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR THE RECORDS SHALL BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE WITH PART VI:
A. A COPY OF ALL NOTICES OF INTENT SUBMITTED TO EPD;
B. A COPY OF EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN REQUIRED BY THE NPDES PERMIT;
C. THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION CONDUCTED IN ACCORDANCE WITH PART IV.A.5. OF THE NPDES PERMIT;
D. A COPY OF ALL SAMPLING INFORMATION, RESULTS AND REPORTS REQUIRED BY THE NPDES PERMIT;
E. A COPY OF ALL INSPECTION REPORTS GENERATED IN ACCORDANCE WITH PART IV.D.4.a. OF THE NPDES PERMIT;
F. A COPY OF ALL VIOLATION SUMMARIES AND VIOLATION SUMMARY REPORTS GENERATED IN ACCORDANCE WITH PART III.D.2. OF THE NPDES PERMIT; AND
G. DAILY RAINFALL INFORMATION COLLECTED IN ACCORDANCE WITH PART IV.D.4.a.(2) OF THE NPDES PERMIT

COPIES OF ALL NOTICES OF INTENT, NOTICES OF TERMINATION, INSPECTION REPORTS, SAMPLING REPORTS, (INCLUDING ALL CALIBRATION AND MAINTENANCE RECORDS AND ALL ORIGINAL STRIP CHART RECORDINGS FOR CONTINUOUS MONITORING INSTRUMENTATION) OR OTHER REPORTS REQUESTED BY THE EPD, EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS, RECORDS OF ALL DATA USED TO COMPLETE THE NOTICE OF INTENT TO BE COVERED BY THIS PERMIT AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHALL BE RETAINED BY THE PERMITTEE WHO EITHER PRODUCED OR USED IT FOR A PERIOD OF AT LEAST THREE YEARS FROM THE DATE THAT THE NOT IS SUBMITTED IN ACCORDANCE WITH PART VI OF THE NPDES PERMIT. THESE RECORDS MUST BE MAINTAINED AT THE PERMITTEE'S PRIMARY PLACE OF BUSINESS OR A DESIGNATED ALTERNATIVE LOCATION ONCE THE CONSTRUCTION ACTIVITY HAS CEASED AT THE PERMITTED SITE. THIS PERIOD MAY BE EXTENDED BY REQUEST OF THE EPD AT ANY TIME UPON WRITTEN NOTIFICATION TO THE PERMITTEE.

SEDIMENT STORAGE REQUIREMENTS:
SEDIMENT STORAGE FOR THE SITE IS PROVIDED BY SILT FENCE IN AREAS SHEET FLOWING OFF SITE AND CHECK DAMS IN SWALES. THE TABLE BELOW PROVIDES A SUMMARY OF THE STORAGE MEASURES. IN ADDITION, THE CONTRACTOR SHALL FOLLOW THESE STRICT GUIDELINES TO PREVENT SEDIMENT FROM LEAVING THE WORK AREAS:

1. PRIOR TO CLEARING, ALL CONSTRUCTION ENTRANCES AND SILT FENCE BARRIERS SHALL BE IN PLACE. SILT FENCE SHALL BE PLACED IN ALL AREAS THAT BOUND STREAMS, CREEKS AND WETLANDS.
CONTRACTOR SHALL ONLY ENTER AND LEAVE FROM INSTALLED CONSTRUCTION ENTRANCES.

2. AT THE END OF EVERY WORK DAY, ALL EXCAVATED AREAS SHALL BE BACKFILLED AND TEMPORARILY MULCHED AND SEEDED FOR STABILIZATION. ALL SILT FENCE DAMAGED IN THAT DAY'S WORK SHALL BE CLEANED OUT AND REPAIRED WHERE NEEDED.

3. ANY DISTURBED AREAS LEFT DORMANT FOR A PERIOD OF GREATER THAN 14 DAYS SHALL BE TEMPORARILY SEEDED.

4. ANY DEWATERING OPERATIONS SHALL NOT DISCHARGE SILTED/MUDDY WATER INTO CREEKS, STREAMS OR DRAINAGE WAYS.

5. NO CREEKS, STREAMS OR DRAINAGE WAYS SHALL BE BLOCKED FOR MORE THAN 1 WORKING DAY.

6. ALL AREAS WHERE STEEP SLOPES (GREATER THAN 4:1) ARE BEING DISTURBED, SLOPE MATTING SHALL BE INSTALLED AFTER BACKFILLING IS COMPLETE.

7. ADHERE TO SPECIFIC SITE NOTES ON EACH PHASE OF THE ESPCP THAT MAY BE MORE RESTRICTIVE THAN PERMIT REQUIREMENTS.

TEMPORARY SEDIMENT STORAGE DETAILS

DISTURBED AREA (AC)	0.71
STORAGE REQUIRED (@ 67 CY/AC)	48
STORAGE PROVIDED (CY)	1498

*SEDIMENT FENCE STORAGE:
TOTAL SILT FENCE LENGTH = 390.32 LF
SILT FENCE HEIGHT = 2'-4"
SEDIMENT CLEAN OUT HEIGHT = 1'-2"
TYPICAL SLOPE = 33.5%
1 LF SILT FENCE = 0.0748 C.Y. STORAGE
PROVIDED STORAGE = 390.32 LF. X (0.0748 C.Y.)
= 29.2 C.Y.

CHECK DAM STORAGE:
NUMBER OF CHECK DAMS = 34
CHECK DAM HEIGHT = 2'
SEDIMENT CLEANOUT HEIGHT = 1'
CHECK DAM AVG WIDTH = 6.0'
TYPICAL SLOPE = 1.5 %
1 CHECK DAM = 200 C.F. STORAGE
PROVIDED STORAGE = 38 X 200 C.F. = 7600 C.F.
= 281 C.Y.

GEORGIA
UNIFORM CODING SYSTEM
FOR SOIL EROSION AND SEDIMENT CONTROL PRACTICES
GEORGIA SOIL AND WATER CONSERVATION COMMISSION

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Cd	CHECKDAM			A small temporary barrier or dam constructed across a swale, drainage ditch or area of concentrated flow.
Ch	CHANNEL STABILIZATION			Improving, constructing or stabilizing an open channel, existing stream, or ditch.
Co	CONSTRUCTION EXIT			A crushed stone pad located at the construction site exit to provide a place for removing mud from tires thereby protecting public streets.
Cr	CONSTRUCTION ROAD STABILIZATION			A travelway constructed as part of a construction plan including access roads, subdivision roads, parking areas and other on-site vehicle transportation routes.
Dc	STREAM DIVERSION CHANNEL			A temporary channel constructed to convey flow around a construction site while a permanent structure is being constructed.
Di	DIVERSION			An earth channel or dike located above, below, or across a slope to divert runoff. This may be a temporary or permanent structure.
Dn1	TEMPORARY DOWNDRAN STRUCTURE			A flexible conduit of heavy-duty fabric or other material designed to safely conduct surface runoff down a slope. This is temporary and inexpensive.
Dn2	PERMANENT DOWNDRAN STRUCTURE			A paved chute, pipe, sectional conduit or similar material designed to safely conduct surface runoff down a slope.
Fr	FILTER RING			A temporary stone barrier constructed at storm drain inlets and pond outlets.
Ga	GABION			Rock filter baskets which are hand-placed into position forming soil stabilizing structures.
Gr	GRADE STABILIZATION STRUCTURE			Permanent structures installed to protect channels or waterways where otherwise the slope would be sufficient for the running water to form gullies.
Lv	LEVEL SPREADER			A structure to convert concentrated flow of water into less erosive sheet flow. This should be constructed only on undisturbed soils.
Rd	ROCK FILTER DAM			A permanent or temporary stone filter dam installed across small streams or drainageways.
Re	RETAINING WALL			A wall installed to stabilize cut and fill slopes where maximum permissible slopes are not obtainable. Each situation will require special design.
Rt	RETRO FITTING			A device or structure placed in front of a permanent stormwater detention pond outlet structure to serve as a temporary sediment filter.
Sd1	SEDIMENT BARRIER			A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles, gravel, or a silt fence.
Sd2	INLET SEDIMENT TRAP			An impounding area created by excavating around a storm drain drop inlet. The excavated area will be filled and stabilized on completion of construction activities.
Sd3	TEMPORARY SEDIMENT BASIN			A basin created by excavation or a dam across a waterway. The surface water runoff is temporarily stored allowing the bulk of the sediment to drop out.
Sd4	TEMPORARY SEDIMENT TRAP			A small temporary pond that drains a disturbed area so that sediment can settle out. The principle feature distinguishing a temporary sediment trap from a temporary sediment basin is the lack of a pipe or riser.
Sk	FLOATING SURFACE SKIMMER			A buoyant device that releases/drains water from the surface of sediment ponds, traps, or basins at a controlled rate of flow.
Spb	SEEP BERM			Linear control device constructed as a diversion perpendicular to the direction of runoff to enhance dissipation and infiltration, while creating multiple sedimentation chambers with the employment of intermediate dikes.

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Sr	TEMPORARY STREAM CROSSING			A temporary bridge or culvert-type structure protecting a stream or watercourse from damage by crossing construction equipment.
St	STORMDRAIN OUTLET PROTECTION			A paved or short section of riprap channel at the outlet of a storm drain system preventing erosion from the concentrated runoff.
Su	SURFACE ROUGHENING			A rough soil surface with horizontal depressions on a contour or slopes left in a roughened condition after grading.
Tc	TURBIDITY CURTAIN			A floating or staked barrier installed within the water (it may also be referred to as a floating boom, silt barrier, or silt curtain).
Tp	TOPSOILING			The practice of stripping off the more fertile soil, storing it, then spreading it over the disturbed area after completion of construction activities.
Tr	TREE PROTECTION			To protect desirable trees from injury during construction activity.
Wt	VEGETATED WATERWAY OR STORMWATER CONVEYANCE CHANNEL			Paved or vegetative water outlets for diversions, terraces, berms, dikes or similar structures.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Bf	BUFFER ZONE			Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the reestablishment of vegetation surrounding an area of disturbance or bordering streams.
Cs	COASTAL DUNE STABILIZATION (WITH VEGETATION)			Planting vegetation on dunes that are denuded, artificially constructed, or re-nourished.
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)			Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP. SEEDING)			Establishing a temporary vegetative cover with fast growing seedlings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)			Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ds4	DISTURBED AREA STABILIZATION (SEEDING)			A permanent vegetative cover using sods on highly erodible or critically eroded lands.
Du	DUST CONTROL ON DISTURBED AREAS			Controlling surface and air movement of dust on construction site, roadways and similar sites.
Fl-Cd	FLOCCULANTS AND COAGULANTS			Substance formulated to assist in the solids/liquid separation of suspended particles in solution.
Sb	STREAMBANK STABILIZATION (USING PERM. VEGETATION)			The use of readily available native plant materials to maintain and enhance streambanks, or to prevent, or restore and repair small streambank erosion problems.
Ss	SLOPE STABILIZATION			A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.
Tac	TACKIFIERS AND BINDERS			Substance used to anchor straw or hay mulch by causing the organic material to bind together.

GA SWCC (Amended - 2013)

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF000350 (EXP 6/30/2024)

TARA BOULEVARD STORM
DRAIN REHABILITATION
8405 TARA BLVD
JONESBORO, GA 30236

CIVIL
EROSION CONTROL NOTES

AS SHOWN
VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
DATE JANUARY 2025
PROJ EEXJ6937
DWG CE-403
SHEET 13 of 18

GA LIC # PEF000350 (EXP 6/30/2026)

ISSUED FOR BID

REUSE OF DOCUMENTS: THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.



© JACOBS 2022. ALL RIGHTS RESERVED.

J:\EEXJ6937\500.DESIGN\410.CAD\712SHSTS

FILENAME: CE-501 EROSION CONTROL NOTES

PLOT DATE: 2024-12-23

PLOT TIME: 1:23 PM




ISSUED FOR BID



REUSE OF DOCUMENTS:

THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.


© JACOBS 2022. ALL RIGHTS RESERVED.



Cd-S **STONE CHECK DAM** NTS **04308**



Su **SURFACE ROUGHENING** NTS **04350**



Rd **ROCK FILTER DAM** NTS **04323**

Jacobs CIVIL

10 10TH STREET, SUITE 1400
ATLANTA, GA 30309
GA LIC # PEF000350 (EXP 6/30/2024)

TARA BOULEVARD STORM
DRAIN REHABILITATION
8405 TARA BLVD
JONESBORO, GA 30236

EROSION CONTROL DETAILS

AS SHOWN
VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
DATE JANUARY 2025
PROJ EEXJ6937
DWG CE-503
SHEET 17 of 18

ISSUED FOR BID

GA LIC # PEF000350 (EXP 6/30/2026)

LEVEL II CERT. # 18856

FILENAME: CE-501 EROSION CONTROL NOTES
PLOT DATE: 2025-01-09
PLOT TIME: 6:22 PM

